

Land Use Planning and Approvals Act 1993

APPLICATION NO.

DA2025/022

LOCATION OF AFFECTED AREA

44 RIVIERA DRIVE, OLD BEACH

DESCRIPTION OF DEVELOPMENT PROPOSAL

MULTIPLE DWELLINGS X 2

A COPY OF THE DEVELOPMENT APPLICATION MAY BE VIEWED AT www.brighton.tas.gov.au AND AT THE COUNCIL OFFICES, 1 TIVOLI ROAD, OLD BEACH, BETWEEN 8:15 A.M. AND 4:45 P.M, MONDAY TO FRIDAY OR VIA THE QR CODE BELOW. ANY PERSON MAY MAKE WRITTEN REPRESENTATIONS IN ACCORDANCE WITH S.57(5) OF THE LAND USE PLANNING AND APPROVALS ACT 1993 CONCERNING THIS APPLICATION UNTIL 4:45 P.M. ON 25/03/2025. ADDRESSED TO THE CHIEF EXECUTIVE OFFICER AT 1 TIVOLI ROAD, OLD BEACH, 7017 OR BY EMAIL

AT

development@brighton.tas.gov.au.

REPRESENTATIONS SHOULD INCLUDE A DAYTIME TELEPHONE NUMBER TO ALLOW COUNCIL OFFICERS TO DISCUSS, IF NECESSARY, ANY MATTERS RAISED.

JAMES DRYBURGH
Chief Executive Officer





SITE NOTES

Property Address: 44 Riviera Drive

Old Beach, 7017

Location: GDA94 MGA55 : 522808E, 5265760N Property ID: 9962130

Title Reference: 181742/265
Site Area: 1624 sqm.
Municipality: Brighton Council
Zone: 8 General Residential

THESE DRAWINGS HAVE BEEN CONSTRUCTED USING SURVEY INFORMATION FROM: 'ROGERSON & BIRCH SURVEYORS'.
File No.: ALLEA01 – 1224001 (07 August 2021).

Contour Interval: 0.25m (or as shown).

Horizontal Datum: GDA2020

GENERAL NOTES:

"THIS PLAN AND ASSOCIATED DIGITAL MODEL IS PREPARED FOR SHANNON & ANGELA ALLEN FROM A COMBINATION OF FIELD SURVEY AND EXISTING RECORDS FOR THE PURPOSE OF DESIGNING NEW CONSTRUCTIONS ON THE LAND AND SHOULD NOT BE USED FOR ANY OTHER PURPOSE.


THE TITLE BOUNDARIES AS SHOWN ON THIS PLAN WERE NOT MARKED AT THE TIME OF THE SURVEY AND HAVE BEEN DETERMINED BY PLAN DIMENSIONS ONLY AND NOT BY FIELD SURVEY. NO MEASUREMENTS OR OFFSETS ARE TO BE DERIVED BETWEEN THE FEATURES ON THIS PLAN AND THE BOUNDARY LAYER. THE RELATIONSHIP BETWEEN THE FEATURES IN THIS MODEL AND THE BOUNDARY LAYERS CANNOT BE USED FOR ANY SET OUT PURPOSES OR TO CONFIRM THE POSITION OF THE TITLE BOUNDARIES ON SITE.

DUE TO THE NATURE OF THE TITLE BOUNDARY INFORMATION, IF ANY STRUCTURES ARE DESIGNED ON OR NEAR A BOUNDARY WE WOULD RECOMMEND A RE-MARK SURVEY BE COMPLETED AND LODGED WITH THE LAND TITLES OFFICE TO SUPPORT THE BOUNDARY DEFINITION.

SERVICES SHOWN HAVE BEEN LOCATED WHERE VISIBLE BY FIELD SURVEY. SERVICES DENOTED AS BEING "PER DBYD ONLY" ARE APPROXIMATE AND FOR ILLUSTRATIVE PURPOSES ONLY. PRIOR TO ANY DEMOLITION, EXCAVATION OR CONSTRUCTION ON THE SITE, THE RELEVANT AUTHORITY SHOULD BE CONTACTED FOR POSSIBLE LOCATION OF FURTHER UNDERGROUND SERVICES AND DETAILED LOCATIONS OF ALL SERVICES.

IF SUBSEQUENT DESIGN IS INTENDED FOR CONSTRUCTION SETOUT, FUTURE SURVEYING SETOUT COSTS ARE INCREASED IF THE DIGITAL DATA PROVIDED IS ROTATED, SCALED OR MOVED.

THIS NOTE FORMS AN INTEGRAL PART OF THE PLAN/DATA. ANY REPRODUCTION OF THIS PLAN/MODEL WITHOUT THIS NOTE ATTACHED WILL RENDER THE INFORMATION SHOWN INVALID.




¥	DEVELOPMENT APPLICATION.	17.02.25
REV.	REV. DESCRIPTION	DATE

Scale:	DWG. No.:
1:500	0130
@ A 3	DA01
Drawn:	Date:
S.Bowling	17.02.25


	Stuart Bowling Building Design B. Environmental Design	Phone: 0418 380 391	Email: stuart.bowling@outlook.com	Licence: CC 7560	ABN: 34 531 056 735
	ξ. B.	R	ᇤ	Ë	AA
,					



1 centimetre on this drawing represents 5 metres on the ground (i.e. 1:500).



WALL LEGEND				
MARK	DESCRIPTION			
	90mm STUDWORK WALL.			
	250mm FACE BRICK VENEER WALL (110/50/90)			




Ą	DEVELOPMENT APPLICATION.	17.02.25
REV.	REV. DESCRIPTION	DATE

DMG. No.: 0130 PROPOSED 2 at No. 44 Rivie OLD BEACH, 7 for Ashley Lid Drawing: PROPOSED FI	Scale: DWG. No.: 1:100 0130 0130 0130 DA03 DA03 DA03 DA03 DA03 017.02.25
---	--

<u>ω</u>		Ω	ဟ
Stuart Bowling Building Design B. Environmental Design	Phone: 0418 380 391 Email: stuart.bowling@outlook.com	Licence: CC 7560	ABN: 34 531 056 735

ORTH	0 1 2 METRES 1 centimetre on this drawing represents	5	
	1 metre on the ground (i.e. 1:100).		




PROPOSED FLOOR AREAS	
PROPOSED HOUSE FLOOR (internal) AREA (N.B.: INCLUDES GARAGE @ 37.4 sgm).	= 195.6 sqm.
TOTAL FLOOR AREA IN SQUARES	= 21.05 SQ.
DWELLING FOOTPRINT (roofed) AREA PATIO ROOFED AREA TOTAL FOOTPRINT (roofed) AREA	= 211.4 sqm. = 15.7 sqm. = 227.1 sqm.

- 0.42mm BMT 'CUSTOM ORB' ROOF SHEETING.
 Pitch: 22.5°.
 Finish: COLORBOND FINISH AS SELECTED.
- 2 COLORBOND CAPPINGS, FLASHINGS, FASCIA & GUTTERING. Finish: COLORBOND FINISH GREY.
- 3 230 x 110 x 76mm FACE BRICKWORK. Colour: BRICK COLOUR AS SELECTED.
- ALUMINIUM WINDOW & DOOR FRAMES.
 Finish: POWDER COATED AS SELECTED.
- (5) 'B & D' PANELIFT (SECTIONAL) GARAGE DOOR.
 Size: 2100 H x 5500 W.
 Finish: COLORBOND FINISH AS SELECTED.
- 6 FRAMELESS 15mm TOUGHENED SAFETY GLASS BALUSTRADE.; Ø 30mm ROUND AL. HANDRAIL.
- STEEL STRUCTURES. PAINT FINISH TO EXPOSED STEEL WORK TO COMPLY WITH PART 3.4.4.4 OF THE BCA ('MODERATE').
- TIMBER SCREENING ON STEEL FRAME.
 90mm HORIZONTAL BOARDS (20mm GAPS).

GENERAL LEGEND

- A. AWNING WINDOW.
- FIXED WINDOW.
- GB. GLAZED BALUSTRADE.
- GD. GLAZED DOOR (direction as indicated).
- . PANELIFT GARAGE DOOR.
- SD. SLIDING DOOR (direction as indicated).
- SV. SMOOTHLINE ROOF VENTILATOR SYSTEM.

WEST ELEVATION



DWELLING 1

SHEET No. **04** OF 08



_				
DWG. No.:	0130	DA04	Date:	17 02 25
Scale:	1:100	@ A 3	Drawn:	S.Bowling


Stuart Bowling Building Design B. Environmental Design	0 391	stuart.bowling@outlook.com		56 735
Sowling	0418 380 391	stuart.b	CC 756	34 531 056 735
Stuart E B. Envir	Phone:	Email:	Licence: CC 7560	ABN.
•				



- 0.42mm BMT 'CUSTOM ORB' ROOF SHEETING. **(1)** Pitch: 22.5°. Finish: COLORBOND FINISH AS SELECTED.
- COLORBOND CAPPINGS, FLASHINGS, FASCIA & GUTTERING. $(\mathbf{2})$ Finish: COLORBOND FINISH GREY.
- 230 x 110 x 76mm FACE BRICKWORK. Colour: BRICK COLOUR AS SELECTED.
- ALUMINIUM WINDOW & DOOR FRAMES. Finish: POWDER COATED AS SELECTED.
- 'B & D' PANELIFT (SECTIONAL) GARAGE DOOR. **5** Size: 2100 H x 5500 W. Finish: COLORBOND FINISH AS SELECTED.
- FRAMELESS 15mm TOUGHENED SAFETY GLASS **(6)** BALUSTRADE.; Ø 30mm ROUND AL. HANDRAIL.
- STEEL STRUCTURES. PAINT FINISH TO EXPOSED STEEL WORK TO COMPLY WITH PART 3.4.4.4 OF THE BCA ('MODERATE').
- TIMBER SCREENING ON STEEL FRAME. (8) 90mm HORIZONTAL BOARDS (20mm GAPS).


GENERAL LEGEND


- AWNING WINDOW.
- FIXED WINDOW.
- GB. - GLAZED BALUSTRADE.
- GD. - GLAZED DOOR (direction as indicated).
- PANELIFT GARAGE DOOR.
- SD. - SLIDING DOOR (direction as indicated).
- SMOOTHLINE ROOF VENTILATOR SYSTEM.






DWELLING 1








- 0.42mm BMT 'CUSTOM ORB' ROOF SHEETING. 1 Pitch: 22.5°. Finish: COLORBOND FINISH AS SELECTED.
- COLORBOND CAPPINGS, FLASHINGS, FASCIA & GUTTERING. **(2**) Finish: COLORBOND FINISH GREY.
- 230 x 110 x 76mm FACE BRICKWORK. Colour: BRICK COLOUR AS SELECTED.
- ALUMINIUM WINDOW & DOOR FRAMES. (4) Finish: POWDER COATED AS SELECTED.
- 'B & D' PANELIFT (SECTIONAL) GARAGE DOOR. 5 Size: 2100 H x 5500 W. Finish: COLORBOND FINISH AS SELECTED.
- FRAMELESS 15mm TOUGHENED SAFETY GLASS **(6)** BALUSTRADE.; Ø 30mm ROUND AL. HANDRAIL.
- STEEL STRUCTURES. PAINT FINISH TO EXPOSED STEEL WORK TO COMPLY WITH PART 3.4.4.4 OF THE BCA ('MODERATE').
- TIMBER SCREENING ON STEEL FRAME. (8) 90mm HORIZONTAL BOARDS (20mm GAPS).

GENERAL LEGEND

- AWNING WINDOW.
- FIXED WINDOW.
- GB. - GLAZED BALUSTRADE.
- GD. - GLAZED DOOR (direction as indicated).
- PANELIFT GARAGE DOOR.
- SLIDING DOOR (direction as indicated).
- SV. SMOOTHLINE ROOF VENTILATOR SYSTEM.





SHEET No. **06** OF 08


 Stuart B B. Envir	Stuart Bowling Building Design B. Environmental Design
Phone:	0418 380 391
Email:	stuart.bowling@outlook.com
Licence:	Licence: CC 7560
ABN.	34 531 056 735




- 1 0.42mm BMT 'CUSTOM ORB' ROOF SHEETING.
 Pitch: 22.5°.
 Finish: COLORBOND FINISH AS SELECTED.
- **2** COLORBOND CAPPINGS, FLASHINGS, FASCIA & GUTTERING. Finish: COLORBOND FINISH GREY.
- 3 230 x 110 x 76mm FACE BRICKWORK. Colour: BRICK COLOUR AS SELECTED.
- 4 ALUMINIUM WINDOW & DOOR FRAMES.
 Finish: POWDER COATED AS SELECTED.
- 'B & D' PANELIFT (SECTIONAL) GARAGE DOOR.
 Size: 2100 H x 5500 W.
 Finish: COLORBOND FINISH AS SELECTED.
- 6 FRAMELESS 15mm TOUGHENED SAFETY GLASS BALUSTRADE.; Ø 30mm ROUND AL. HANDRAIL.
- STEEL STRUCTURES. PAINT FINISH TO EXPOSED STEEL WORK TO COMPLY WITH PART 3.4.4.4 OF THE BCA ('MODERATE').
- TIMBER SCREENING ON STEEL FRAME.
 90mm HORIZONTAL BOARDS (20mm GAPS).


GENERAL LEGEND

- A. AWNING WINDOW.
- FIXED WINDOW.
- GB. GLAZED BALUSTRADE.
- GD. GLAZED DOOR (direction as indicated).
- PANELIFT GARAGE DOOR.
- SD. SLIDING DOOR (direction as indicated).
- V. SMOOTHLINE ROOF VENTILATOR SYSTEM.







SHEET No. **07** OF 08



4		
DWG. No.: 0130 DA07	Date:	17.02.25
Scale: 1:100 @ A3	Drawn:	S.Bowling


Stuart Bowling Building Design B. Environmental Design	0418 380 391	stuart.bowling@outlook.com	Licence: CC 7560	34 531 056 735
Stuart B. Env	Phone:	Email:	Licence	ABN:






SUN SHADOW PLAN - 21st JUNE 2022 - 9am 1:250

WINTER SOLSTICE 2022 AZIMUTH = 44°59'04" ALTITUDE = 10°19'56"



SUN SHADOW PLAN - 21st JUNE 2022 - 11am


WINTER SOLSTICE 2022 AZIMUTH = 17°54'07" ALTITUDE = 21°38'28"



SUN SHADOW PLAN - 21st JUNE 2022 - 10am 1:250

WINTER SOLSTICE 2022 AZIMUTH = 31°38'23" ALTITUDE = 17°02'28"

SUN SHADOW DIAGRAM NOTES THESE SUN SHADOWS HAVE BEEN CONSTRUCTED USING **INFORMATION FROM: AUSTRALIAN GOVERNMENT - GEOSCIENCE AUSTRALIA** http://www.ga.gov.au/geodesy/astro/smpos.jsp **HOBART, TASMANIA (AEST - Australian Eastern Standard Time):** Latitude: 42°53'00" South Longitude: 147°17'00" East Winter Solstice (21 June 2022) - Sunrise: 07:42 Az. 58°03'42" Al. 0° 51' 29" - Solar Noon: 12:12 Az. 00°09'09" Al. 23°42'49" - Sunset: 16:43 Az. 301°58'32" Al. 00°15'29"




A. DEVELOPMENT APPLICATION. REV. DESCRIPTION

	at No. 44 Riviera Drive,	PROPOSED 2 x DWELLINGS	
	OLD BEACH, 7017 for Ashley Liddelow	at No. 44 Riviera Drive, OLD BEACH, 7017 for Ashley Liddelow	PROPOSED 2 x DWELLINGS at No. 44 Riviera Drive, OLD BEACH, 7017 for Ashley Liddelow
Drawing:	OLD BEACH, 7017	at No. 44 Riviera Drive, OLD BEACH, 7017	PROPOSED 2 x DWELLINGS at No. 44 Riviera Drive, OLD BEACH, 7017
for Ashley Liddelow Drawing:		at No. 44 Riviera Drive,	PROPOSED 2 x DWELLINGS at No. 44 Riviera Drive,

DWG. No.: 0130 SS01
0130 SS01
Scale: 1:250 @ A3 Drawn:

Stuart Bowling Building Design B. Environmental Design	Phone: 0418 380 391 Email: stuart.bowling@outlook.com Licence: CC 7560 ABN: 34 531 056 735
---	--



UNIT DEVELOPMENT 44 RIVIERA DRIVE OLD BEACH

DRAWING INDEX

C001 DRAWING INDEX

C002 GENERAL NOTES 1

C003 GENERAL NOTES 2

C004 SAFETY IN DESIGN

C101 LEVELS & GRADES

C102 SITEWORKS DETAILS & NOTES

C103 SERVICES PLAN

C104 LONGITUDINAL SECTION

C105 CROSS SECTIONS PLAN 1

C106 CROSS SECTIONS PLAN 2

C107 CROSS SECTIONS PLAN 3

C108 DETAILS PLAN 1

C109 VEHICLE TURNING PLAN 1

C110 VEHICLE TURNING PLAN 2

LEGEND	. 0		
	• 00		Existing surface level (surveyed)
	• 9.60 E	X	Existing surface level (interpolated)
	• 9.80		Proposed bulk earthworks level
	• 9.80		Proposed finished surface level
———EX W	——EX W————	EX W	Existing water supply external to building
w	w	w	Proposed water supply external to building
———EX FS———	—EX FS———	——EX FS ———	Existing fire supply
FS	—FS	—FS——	Proposed fire supply
———EX S	—EX S———	——EX S ———	Existing sewer drain
 \$	—s—	—s——	Proposed sewer drain
GW	—GW——	—GW——	Proposed sewer drain (greasy waste)
тw	—тw——	—тw——	Proposed sewer drain (trade waste)
———EX SW———	—EX SW———	——EX SW———	Existing stormwater drain
sw	—sw——	—sw——	Proposed stormwater drain
			Proposed stormwater (larger)
			Proposed DN100 ag. drain and geofabric sock

F	REV	DESCRIPTION	DATE
	0	BUILDING APPROVAL	7/09/22
	1	REVISED FOR BUILDING APPROVAL	17/02/25

Saltmarsh & Escobar Consulting Engineers

Leigh 0400 024 463
Noe 0416 074 935
info@learden.com

CLIENT:	SHEET:	DRAWN:	DESIGNED:	VERIFIED:	DA	TE:
LIDDELOW	DRAWING INDEX	NE	NE		-	12/04/2
ADDRESS:	PROJECT NAME:	SCALE:	N.T.S	SIZE:	А3	
	UNIT DEVELOPMENT					I
44 RIVIERA DRIVE		S&E REF:		DRAWING:		REVISIO
44 RIVIERA DRIVE OLD BEACH	BUILDING APPROVAL	220	038	C00	1	1

GENERAL

- 1. These drawings shall be read in conjunction with all other contract drawings and specifications. Any discrepancies shall be referred to S&E for
- Setting out dimensions and levels shown on the drawings shall be verified by the Contractor prior to commencement.
- Dimensions shall not be obtained by scaling these drawings.
- During construction the Contractor shall maintain excavations and structures in a stable condition and ensure that no part is overstressed under construction activities.
- The contractor is responsible for the creation and maintenance of temporary site accesses. Strengthening of design pavements to carry construction vehicles (in excess of the design allowance) shall be at the contractor's
- Location and verification of existing services is the contractor's responsibility. Refer any services discovered onsite which are not shown on the drawings, or are in a different location to that shown to S&E. Seek confirmation from S&E that redundant services are able to be sealed and abandoned prior to
- Protect all existing services and other infrastructure from damage during construction. Should damage occur, advise S&E immediately along with details of proposed remedial action. The cost of remedial work (including redesign if required) shall be borne by the contractor.
- The contractor is responsible for undertaking whatever dilapidation surveys of existing buildings/infrastructure they consider necessary prior to construction commencing, and consultation with adjoining land owners to minimise disruption to services/access etc. during construction.
- All surplus construction materials (including excess cut and fill material) shall be removed from the site (unless instructed otherwise) at completion.
- 10. Survey information has been supplied by Leary & Cox Surveyors for the purposes of preparing the design drawings. All other survey required to setout and construct the works shall be provided by the contractor.
- 11. All works are to be undertaken by the contractor and his subcontractors unless noted otherwise on the drawings.
- 12. Proposed changes to the design of any part of the works shall be submitted to S&E for review. The contractor shall bear all costs associated with the design change.
- 13. On completion, the contractor is to supply as-constructed drawings (prepared by a licensed surveyor in accordance with AS1100.401) and full service manual in both hard copy (3 sets) and electronic (.pdf and .dwg)
- 14. The contractor is to allow for all testing of raw materials and constructed works that is required to demonstrate compliance with the nominated Australian Standards, specifications, and standard drawings.

EARTHWORKS

- All earthworks shall be in accordance with AS3798 "Guidelines on earthworks for commercial and residential developments" with testing methods in accordance with AS1289 "Methods of testing soils for engineering purposes".
- E2. All existing topsoil, vegetation and debris under the building and paved areas shall be stripped to a minimum of 300mm unless noted otherwise. Top soil to be stockpiled as directed, and vegetation and debris removed from site unless noted otherwise. Tree stumps shall be grubbed and holes filled with approved compacted fill.
- For excavation purposes, rock is defined as hard or strongly cemented beds or masses which cannot be ripped at a production rate exceeding 3 m³ per hour using a standard 20 tonne excavator attached with a rock breaker.
- Any interface between cut and fill shall be no steeper than 1V:3H. Cut horizontal benches for any fill placed on ground steeper than 1V:3H.
- All excavations shall be inspected by the Engineer and/or the Local Authority before proceeding any further. Inspection and testing shall occur after each lift during filling. Testing (in accordance with Table 8.1 of AS3798.1) shall be arranged by the contractor such that results are available at time of inspection.
- Subgrade shall be compacted to achieve 98% standard density ratio for cohesive soil, and 75% density index for cohensionless soil. Prior to filling, subgrade is to be proof roll tested. All proof roll testing is to be witnessed by the Engineer. The test shall consist of witnessing soil deflection from the tyre of a single rear axle truck driven at walking speed with a minimum 8 tonne rear axle load and a tyre pressure of 550 kPa. The allowable deflection of subgrade shall not be more than is just visible to an observer standing still as the test vehicle passes, and no visible movement is allowed for sub-base and base tests. Other vehicles that may be allowed by the Engineer are a 12 tonne static roller with 6 tonne/m load, or 20 tonne plant with 450 kPa tyres and greater than 0.035 m² contact area per tyre.
- Fill shall be placed in horizontal layers of 200 to 300 mm deep loose measurement, unless testing can demonstrate to the Engineer that compaction is adequate within larger lifts. Compact each layer of fill within 1% of its optimum moisture content. Maximum particle size is two thirds depth of each lift. Each layer is to be proof roll tested, using nuclear density testing as directed to achieve 98% standard density ratio. For material 60 mm and courser, in-lieu of density testing a test by deflection to done using spot level difference at representative locations before and after rolling three times with 12 tonne roller, with acceptable differences being less than 2 mm.
- Cohesionless (granular) fill to be used unless otherwise approved by the Engineer. Cohesionless (granular) fill to have less than 15% passing the 75 micron sieve, with grading curves submitted for approval. Cohesionless fill shall be compacted to the requirements of Table 5.1 of AS3798. Cohesive fill shall have a minimum 4 day soaked CBR of 5% and a maximum CBR swell of 1%. Minimum standard density ratios for cohesive material shall be as per Table 5.1 of AS3798. Reactive clay shall have a maximum standard density ratio of 100%. Landscaping zones should be compacted to standard density ratio of 85% unless noted otherwise.

ROADWORKS

- All works to be in accordance with Local Government Association Tasmania -IPWEA standard drawings.
- It is assumed roads accessing the development site are adequate to take the design traffic load during the design life of 40 years.
- Pavement depth shall be as shown on the typical cross section but shall be subject to CBR testing of subgrade or proof rolling, with final depth shall be confirmed by the Engineer.
- Kerb and channel shall be formed on a minimum of 100mm sub-base (see note R7) which shall extend a minimum 150 mm beyond the back of the kerb.
- Subsoil drains shall be formed as shown on the drawings and in accordance with AS/NZS3500.
- R7. All radii are to the back of kerb.
- The road profile and cross-fall shall be finished to the satisfaction of the Engineer and shall be to line and level indicated on the drawings, free of any local high or low areas which may hold water.
- All gravel to comply with the following DIER specifications:

Base course: R40 class A - 19 mm Fine Crushed Rock (FCR) Sub-base course: Sub-base 1 - 40 mm FCR

- Sub-base shall have a minimum modified density ratio of 95% and base to have a minimum modified density ratio of 98%, with nuclear density test results available at proof roll inspection. Tests to be taken at a frequency based on AS3798 (typically the greater of four tests per inspection or one test per 1000
- R11. Proof roll shall be with a Truck using a single rear axle, tyres at 550 kPa, and the load over rear axle shall be 8 tonnes.
- All landscaped areas affected by the works are to be reinstated to match existing. Refer Landscape Architect for specific requirements.
- Concrete footpaths and driveways are to be constructed to the Municipal Standard drawings unless noted otherwise.

APPROVALS

- 1. Prior to construction commencing, the Contractor is responsible for ensuring that a valid building and engineering permit is in place for the work & that the relevant authorities are notified and allowed to inspect at the nominated hold points.
- 2. Unless nominated otherwise, the following inspection regime is to be adopted:
 - Road formations:

Inspection of subgrade, subbase and base lifts, kerbing and seal undertaken by S&E:

Stormwater:

Inspection of stormwater infrastructure to be owned by the local council undertaken by the local council;

• Sewer and water:

Sewer and water infrastructure to be owned by TasWater inspected and self certified by civil contractor or their subcontractor;

• As-built services surveys

Water, sewer, stormwater surveys undertaken by contractor's licensed surveyor (depth of water reticulation recorded prior to backfilling);

DESIGNED:

N.T.S

DATE: 12/04/22

REVISION:

Α3

DRAWING.

C002

• Installation of other in-ground services

Power, communications, gas etc. undertaken by the relevant managing authority.

- 3. A minimum of 24 hours notice is required for S&E to attend the site. Do not rely upon facsimile or email to communicate requests - make contact with our office to confirm
- Inspection of road formations may involve proof rolling with a test vehicle. Confirm with S&E and ensure a suitable vehicle is available at the time of inspection.
- Photographic documentation is not an adequate basis to proceed beyond a hold point unless approved by S&E.

	REV	DESCRIPTION	DATE	
	0	BUILDING APPROVAL	7/09/22	
	1	REVISED FOR BUILDING APPROVAL	17/02/25	
.=				

Leigh 0400 024 463 Noe 0416 074 935

IENT:	SHEET:	DRAWN:	DESIGNED
LIDDELOW	GENERAL NOTES 1	NE	
		SCALE:	_
DDRESS:	PROJECT NAME:		N
44 RIVIERA DRIVE	UNIT DEVELOPMENT	S&E REF:	
OLD BEACH	ISSUE: BUILDING APPROVAL	220)38

STORMWATER

- SW1. All works to be in accordance with Local Government Association Tasmania IPWEA standard drawings.
- SW2. All materials and workmanship shall be in accordance with the local authority's specifications, standard drawings, by-laws and AS/NZS3500.
- SW3. Pipe and channel infrastructure has been designed to convey 20 year average recurrence interval (ARI) storms, with overland flow paths provided for 100 year ARI storms. It is assumed that water flowing onto the development site is contained within Local Authority infrastructure for 20 year ARI storms and the road reserve for 100 year ARI storms. For storms up to 24 hours duration, an allowance of 25% extra rainfall intensity has been made due to protected future climate change in Tasmania (above the 30-years-to-1983 intensities compared to projected ones in approximately 2080).
- SW4. Stormwater trenches, pipe bedding and back filling to comply with the Concrete Pipe Association of Australia installation requirements for type HS2 support.
- SW5. Below ground pipework and fittings to be PVC-U SWHD, joints shall be of solvent cement type or flexible joints made with approved rubber rings.
- SW6. Minimum grade of paved areas and pipework shall be 1 in 100. Paved areas ideally shaped to drain to grated pits and trenches without ponding (acceptable limit is 3 mm under a 2 m straight edge).
- SW7. Surface water drains, catchpits/grated pits, and junction boxes shall be constructed as detailed or as specified by the manufacturer. Grated pits to have 150 mm sumps. Pits and lids to be Class A in non-trafficked areas, and pre-cast concrete Class C elsewhere. Convey trench water into pits/manholes through weep holes on upstream side using 2 m of DN100 ag-drain with filter sock.
- SW8. Install all agricultural drains to the requirements of AS/NZS3500 and part 3.1.2. of the BCA.
- SW9. All hydraulic connections and tapings to be clear of driveways and trafficked areas.
- SW10. Where both stormwater and sewer lines are along rear and side boundaries they shall be located to fit inside a 3.0 m easement unless noted otherwise. A single line shall fit within a 2.0 m easement.
- SW11. All manholes to be located clear of future fencelines.
- SW12. Property connections to be clear of driveways and clear of future fencelines.

SEWER

- S1. All works in accordance with the Sewerage Code of Australia W.S.A. 02-2002-2.3 M.R.W.A. Edition Version 1 and TasWater's Supplement (Draft 05 issued May 2013).
- S2. Property connections to be DN100 PVC-U with a minimum grade of 1 in 60. (Refer above code WSAA SEW-1106). To be located clear of trafficked areas, driveways and fences.
- S3. Where both stormwater and sewer lines are along a rear or side boundary they shall be located in an easement that wholly contains both services. Refer TasWaters Supplement Clause 4.2.5. and Clause 4.4.5.2 for clearances to other services.
- S4. All manholes to be located clear of future fence lines with end of lines to be 1.2 m past the boundary for any future extension. Refer Clause 4.3.6.

WATER

- W1. All works in accordance with the Water Supply Code of Australia W.S.A. 03-2011-3.1 M.R.W.A. Edition Version 2 and TasWater's Supplement (Draft 03 issued May 2013)
- W2. Single house connections to be DN25 HDPE class 16 to TasWater's standard drawing TW-SD-W-20 series with meter, backflow device and box to each lot. Located 500 mm inside boundary and 500 mm from edge of driveway on middle side of lot.
- W3. All water mains to be tested and witnessed by the relevant water corporation inspector to static pressure plus 50% prior to backfilling.
- W4. All hydraulic connections and taping to be clear of driveways and trafficked areas.
- W5. For minimum cover over pipes refer to Clause 7.4.2 of the above Supplement.
- W6. All trenches under trafficked areas to be back filled with approved compacted FCR including future driveway extensions.
- W7. Flushing of mains to be carried out in accordance with the manufacturer's recommendations.
- W8. Electromagnetic tracker tape to be placed in all water main trenches above the pipe.
- W9. Taping and takeoffs to be separated by at least 1000 mm.
- W10. Water mains to be bedded on 80 mm approved 7 mm clean metal.
- W11. Concrete anchor blocks to be provided at all sudden changes of direction, both vertically and horizontally at tees and end of lines. Refer to above code drawings MRWA-W-205B and MRWA-W-205C.
- W12. Road crossings:

DN100 PVC-U conduits for all HDPE.

DICL with PE wrapping sleeve as per City West Water approved products catalogue.

W13. For valve and hydrant surface box markings refer to Clause 8.10.3 of the above Supplement. Hydrant road markings to comply with the Institute of Municipal Engineering Australia Tasmania Division document titled Fire Hydrant Guidelines - refer section 8. All valves and hydrants to be resilient seated powder coated class 16 and all components to be DN100.

RETAINING WALLS

- RW1. Retaining walls shall be constructed in accordance with AS4678-2002.
- RW2. Backfill to walls shall be an approved granular material (clay shall not be used). A 300mm wide free draining drainage layer shall be provided behind the wall.
- RW3. Provide a suitable waterproofing system to the rear of the wall, unless confirmed otherwise.
- RW4. The wall shall be drained with 100mm slotted PVC pipe installed at 1% fall (minimum) and be connected to the stormwater disposal system (or weepholes installed at the base where appropriate).
- RW5. The Contractor shall maintain excavated batters at a stable slope and provide shoring to steeper excavations until construction and backfilling of the wall is complete.
- RW6. Retaining walls that rely on other structural elements for stability shall be provided with temporary support until after these elements have been constructed.
- RW7. The Contractor shall allow a suitable curing period prior to backfilling. Backfilling shall be performed in a controlled manner which will not impose excessive stress on the wall.

CONCRETE

- C1. All workmanship and materials shall be in accordance with AS3600.
- C2. Concrete grades (UNO on drawings):

ELEMENT	Grade
General	N25
Footings	N20
Blinding	N15
Pavement	N25

- C3. Concrete shall not be poured when the site temperatures are below 5°C.
- C4. Concrete shall be cured by continuous wetting (water spray, ponding or irrigated hessian) or application of an impermeable membrane (secured plastic or curing compound) for an appropriate period of time (not less than 3 days). In hot dry and windy weather spray the surface with aliphatic alcohol while concrete is plastic, water cure for at least 24 hours then cover with impermeable membrane (or continue to water cure) for a further 2 days.
- C5. Construction joints shall be properly formed and used only where shown or specifically approved by the Engineer. Sawn joints shall be cut one third of the way through a slab, through the top mesh for 100 mm slabs and in thicker slabs the mesh shall be placed to avoid being cut. Unless noted elsewhere, sawn joints shall be at 6 m centres at points of changes in geometry and construction joints at 24 m, with jointed areas to have a plan aspect ratio no slenderer than 1:2.
- C6. Cover to reinforcement shall be 40 mm for slabs and 50 mm for footings.
- C7. Reinforcement shall be deformed, 500 MPa yield strength, normal (N) ductility in accordance with AS/NZS4671 for bars and low (L) ductility for mesh.
- C8. Formwork shall be designed and constructed in accordance with AS3610, and is the responsibility of the contractor.

12/04/22

REVISION

C9. All steel items to be cast into the concrete surface shall be hot dip galvanised.

REV	DESCRIPTION	DATE
0	BUILDING APPROVAL	7/09/22
1	REVISED FOR BUILDING APPROVAL	17/02/25

CLIENT:		SHEET:	DRAWN:	DESIGNED:	VERIFIED:	D
	LIDDELOW	GENERAL NOTES 2	N	E NE		-
			SCALE:		SIZE:	
ADDRESS:		PROJECT NAME:		N.T.S		A3
	44 RIVIERA DRIVE	UNIT DEVELOPMENT	S&E REF:		DRAWING:	
OLD BEACH	ISSUE: BUILDING APPROVAL	22	038	C00	3	

CONSTRUCTION RISK ASSESSMENT

THIS CONSTRUCTION RISK ASSESSMENT IS TO HIGHLIGHT TO THE BUILDER, SUB CONTRACTORS AND SUB CONSULTANTS THE MAIN RICK FACTORS IN UNDERTAKING THE CONSTRUCTION OF THE WORKS TO WHICH THESE NOTES FORM PART OF THE WORKING DRAWINGS.

THIS ASSESSMENT IN NOT EXHAUSTIVE AND THE BUILDER IS TO UNDERTAKE THEIR OWN SIMILAR ASSESSMENT AND MAINTAIN APPROPRIATE RISK MANAGEMENT ACTIVITIES FOR THE DURATION OF THE CONSTRUCTION PERIOD.

IT IS THE BUILDER RESPONSIBILITY TO ENSURE ALL PERSONNEL THAT ENTER THE CONSTRUCTION SITE ARE BRIEFED ON THE SPECIFIC SAFETY HAZARDS AND RISKS ASSOCIATED WITH THE DAILY ACTIVITIES.

WORKS ARE TO BE CARRIED OUT IN ACCORDANCE WITH CURRENT WORK AND WORK AND HEALTH SAFETY REQUIREMENTS.

THIS SITE SPECIFIC RISK ASSESSMENT ASSIGNS A RISK RATING ACCORDING TO THE FOLLOWING MATRIX. THIS ASSIGNS THE MAIN CONSTRUCTION TASK A LIKELIHOOD (L), SEVERITY (S) AND RESULTING RISK RATING (R).

S&E HAS TO THE BEST OF THEIR ABILITY, UNDERTAKEN TO IDENTIFY POTENTIAL CONSTRUCTION HAZARDS AND MINIMIZE THE RISK POTENTIAL TO THOSE INVOLVED WITH THE CONSTRUCTION OF THESE WORKS.

				Severity (S)							
			н	Fatality, major injury causing long term disability	M	Injury or illness causing short term disability	L	Other injury or illness			
Likelihood (L)	н	Certain or near certain		3	5		2				
	M	Reasonably likely		3		2		1			
	L	Very seldom		2		1		1			

Risk Rating (R)

Action required by contractor to mitigate or eliminate risk.

Medium risk

Action required by contractor to reduce risk.

No direct action required by

the contractor.

Category	Hazard (factor/event)	Consequence Description	Likelihood	Consequence	Uncontrolled Risk Rating	Control Measure	Control type	Likelihood	Consequence	Controlled Risk Rating	nu
DEMOLITION (prior to co					RISK RATING					Rating	nu
DEMOLITION (prior to co	working at heights	Fall leading to serious injury and/or fatality				Work in accordance with Safe Work Australia Codes of					
General	securing at unidute	on reading to serious injury and/or fatality	Possible	Extreme		Practice: Preventing Falls in Housing Construction,	Administration	Rare	Extreme	М	
	Plant & equipment	Serious injury and/or fatality to workers, public		-		Managing the Risk of Falls in the Workplace Work in accordance with Safe Work Australia Code of		+	-		
			Possible	Extreme	н	Practice: Managing Risks of Plant in the Workplace	Engineering	Rare	Extreme	М	
	Contamination / Hazardous substances	Serious injury and/or fatality to workers, public	Unlikely	Extreme	н	Undertake contamination investigation/audit. Work in accordance with Safe Work Australia Code of Practice:	Isolation	Rare	Extreme	м	
			Otsikely	Excense	."	Demolition Work	nonduon	nare	Exceme	W	
	Erosion	Uncontrolled erosion pollutes stormwater systems and/or watercourses downstream	Likely	Minor	М	Install erosion protection and follow Stormwater Management Plan (SWMP)	Engineering	Rare	Minor	L	
	Stormwater services	Damage to existing service				Dial before you dig (1100) & locate existing services					
Existing Services			Possible	Minor	L	on site prior to commencing work. Work in accordance	Isolation	Rare	Minor	L	
						with local authority guidelines & Safe Work Australia Code of Practice: Demolition Work					
· ·	Sewer services	Damage to existing service				Dial before you dig (1100) & locate existing services					
			Possible	Minor	L	on site prior to commencing work. Work in accordance with local authority guidelines & Safe Work Australia	Isolation	Rare	Minor	L	
						Code of Practice: Demolition Work					
	Water supply	Damage to existing service and injury to worker and/or undermining of adjacent structure				Dial before you dig (1100) & locate existing services on site prior to commencing work. Work in accordance					
		and/or undernining or adjacent structure	Possible	Extreme		with local authority guidelines & Safe Work Australia	Isolation	Extremely Rare	Extreme	L	
	Electrical services					Code of Practice: Demolition Work					
	Electrical services	Electrocution and serious injury/fatality				Dial before you dig (1100) & locate existing services on site prior to commencing work. Work in accordance					
			Possible	Extreme		with local authority guidelines & Safe Work Australia	Isolation	Extremely Rare	Extreme	L	
						Code of Practice: Demolition Work					
CONSTRUCTION											
General	Working at heights	Fall leading to serious injury and/or fatality	Possible	Extreme		Work in accordance with Safe Work Australia Codes of Practice: Preventing Falls in Housing Construction,	Administration	Rare	Extreme	м	
Gendal			rossible	extreme	н	Managing the Risk of Falls in the Workplace	Auministration	nare	extreme	M	L
	Plant & equipment	Serious injury and/or fatality to workers, public	Possible	Extreme	н	Work in accordance with Safe Work Australia Code of	Engineering	Rare	Extreme	М	
	Contamination/hazardous	Serious injury and/or fatality to workers, public	- · · ·	<u> </u>		Practice: Managing Risks of Plant in the Workplace Undertake contamination investigation/audit. Work in		_			
	substances	, ,	Unlikely	Extreme		accordance with Safe Work Australia Code of Practice:	Isolation	Rare	Extreme	М	
	Construction loading	Construction loads (due to traffic, back		-		Demolition Work Limit construction loads to the documented design loads.		_			
		propping etc.) on structures exceed design load	Unlikely	Extreme		Engage a Temporary Works Engineer to provide specific	Administration	Rare	Extreme	м	
		allowances, collapse, serious injury and/or fatality	CIRINETY	- Au eine		advice where higher construction loads are required.	roundinguiduoni	Naid	Laveille		
-	Manual handling of heavy	Major Injury				Make sure to use proper lifting techniques, Use					
	materials & equipment		Possible	Major		appropriate lifting equipment and adhere to recognised	Administration	Rare	Major	L	
	Use of vibrating equipment (rock	Damage to neighbouring property, possible				safe work procedures. Dilapidation survey prior to work starting, use		-			
	breaker, vibrating roller etc.)	minor injury	Possible	Major		appropriate sized plant and monitor neighbouring	Administration	Rare	Major	L	
	adjacent to existing buildings/infrastructure					property					
	Construction in confined spaces	Entrapment, suffocation leading to serious				Entry to confined spaces by permit only and by trained		1.			
		injury and/orfatality	Possible	Extreme		personnel. Work in accordance with Safe Work Australia Code of Practice: Confined Spaces	Administration	Extremely Rare	Extreme	L	
	Construction traffic	Uncontrolled site traffic entering and leaving	Unlikely	Extreme	н	Develop and implement site specific traffic management	Administration	Rare	Extreme	М	
	Working in remote or extreme	site causes serious injury/fatality unreliable or infrequent access to essential				plan and direct traffic on site Develop and implement site specific disaster plan,					
	environment	services and supplies in the event of an	Unlikely	Extreme		induding communication and transport plans	Administration	Extremely Rare	Extreme	L	
Excavation	Extreme weather/natural disaster		Unlikely	Extreme	н	Prepare site and monitor weather, and secure site and	Administration	Extremely Rare	Extreme	L	
	Deep excavations (>1.5m deep)	site unsafe. Serious injury/fatality Collapse of excavation leading to serious injury	- Community			evacuate in a timely manner as required Work in accordance with Safe Work Australia Code of	710111111011011	and annexy mane			
	beep excavations (-1.5in deep)	and/or fatality	Possible	Extreme		Practice: Excavation Work. Engage a Temporary Works	Engineering	Extremely Rare	Extreme	L	
						Engineer to provide specific shoring advice.					
	Shallow excavations (<1.5m deep)	Collapse of excavation, serious injury	Possible	Moderate	М	Work in accordance with Safe Work Australia Code of Practice: Excavation Work.	Administration	Extremely Rare	Moderate	L	
	Steep slopes	Collapse of excavation leading to serious injury				Work in accordance with Safe Work Australia Code of					
		and/or fatality	Possible	Extreme		Practice: Excavation Work. Engage Geotechnical	Administration	Extremely Rare	Extreme	L	
						Engineer &/or Temporary Works Engineer to provide specific advice					
	High level spread footings	Fall, injury				Work in accordance with Safe Work Australia Code of					
In-ground concrete			Possible	Moderate	М	Practice: Excavation Work. Provide reinforcement caps to all starter bars	Administration	Rare	Moderate	L	
	Bored, cast insitu piles/piers	Fall leading to serious injury and/or fatality				Work in accordance with Safe Work Australia Code of					
			Possible	Extreme		Practice: Excavation Work. Pour concrete as soon as	Administration	Extremely Rare	Extreme	L	
	Lift overrun shafts	Fall leading to serious injury and/or fatality				practical after excavation Work in accordance with Safe Work Australia Code of					
		, and a laterty	Possible	Major		Practice: Excavation Work. Provide reinforcement caps	Administration	Extremely Rare	Major	L	
			, costole	major		to all starter bars or other potential impalement		- Assessery naire	major	,	
-	Temporary support until slabs are	Collapse leading to serious injury and/or		 		hazards. Do not backfill wall prior to completion of supporting		1			
Retaining walls	poured	fatality	Almost Certain	Extreme		structure and adequate curing time. Engage Temporary	Engineering	Extremely Rare	Extreme	L	
						Works Engineer to provide specific advice if early backfilling required.	J				
	Temporary support whilst	Collapse leading to serious injury and/or				Do not back fill until concrete footing and grout fill to					
	backfilling	fatality	Possible	Extreme		wall have reached 28 day strength. Alternatively	Engineering	Extremely Rare	Extreme	L	
				1		engage a Temporary Works Engineer to provide specific advice.			1		
		Collapse leading to serious injury and/or				Install without accessing rear of wall. Alternatively					
	etc. behind wall	fatality	Possible	Extreme		engage a Temporary Works Engineer to provide	Administration	Extremely Rare	Extreme	L	
	Transport, handling and erection	Collapse leading to serious injury and/or		<u> </u>		specific advice Work in accordance with the National Code of Practice for		 	<u> </u>		
Precast concrete	of precast elements	fatality	Likely	Catastrophic		Precast, Tilt-up and Concrete Elements in Buildings.	Engineering	Extremely Rare	Catastrophic	М	
<u> </u>	Temporary support of precast	Collapse leading to serious injury and/or		-		Engage a Temporary Works Engineer to provide specific Work in accordance with the National Code of Practice for		-			
	elements	Collapse leading to serious injury and/or fatality	l lhal	Catastronkis		Precast, Tilt-up and Concrete Elements in Buildings.	Administration	Pytromol- Pa-	Catastronki	м	
			Likely	Catastrophic		Engage a Temporary Works Engineer to provide specific	Administration	Extremely Rare	Catastrophic	M	
	1	Collapse leading to serious injury and/or				advice Engage a Temporary Works Engineer to provide specific					
	Formwork support		Possible	Catastrophic		advice	Engineering	Extremely Rare	Catastrophic	М	
Suspended concrete		fatality				Engage a Temporary Works Engineer to provide specific	Engineering	Extremely Rare	Catastrophic	М	
Suspended concrete	Formwork support Back propping	Collapse leading to serious injury and/or	Unlikely	Catastrophic		advice			<u> </u>		
Suspended concrete				Catastrophic	E	advice Protect live edges and/or install temporary floors. Work in					
Suspended concrete	Back propping	Collapse leading to serious injury and/or fatality		Catastrophic	E H	Protect live edges and/or install temporary floors. Work in accordance with Safe Work Australia Codes of Practice:	Isolation	Extremely Rare	Extreme	L	
Suspended concrete	Back propping	Collapse leading to serious injury and/or fatality	Unlikely	<u> </u>		Protect live edges and/or install temporary floors. Work in accordance with Safe Work Australia Codes of Practice: Preventing Falls in Housing Construction, Managing the	Isolation	Extremely Rare	Extreme	L	
Suspended concrete	Back propping	Collapse leading to serious injury and/or fatality	Unlikely	<u> </u>		Protect live edges and/or install temporary floors. Work in accordance with Safe Work Australia Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Workplace Protect live edges and/or install temporary floors Work in	Isolation	Extremely Rare	Extreme	L	
Suspended concrete	Back propping Live edges	Collapse leading to serious injury and/or fatality Fall leading to serious injury and/or fatality	Unlikely	<u> </u>		Protect Live edges and/or install temporary floors. Work in accordance with Safe Work Australia Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Workplace Protect Live edges and/or install temporary floors Work in accordance with Safe Work Australia Codes of Practice:	Isolation	Extremely Rare	Extreme Extreme	L	
Suspended concrete	Back propping Uwe edges Openings in formwork	Collapse leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Fall leading to serious injury and/or fatality	Unlikely Possible	Extreme	н	Protect live edges and/or install temporary floors. Work in accordance with Safe Work Australia Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Workplace Protect live edges and/or install temporary floors Work in accordance with Safe Work Australia Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Workplace				L L	
Suspended concrete	Back propping Live edges Openings in formwork Transport, handling and erection	Collapse leading to serious injury and/or fatality fall leading to serious injury and/or fatality fall leading to serious injury and/or fatality fall leading to serious injury and/or fatality Collapse of structure or fall from height, leading	Unlikely Possible	Extreme	н	Protect live edges and/or install temporary floors. Workin scordance with Safe Work Australla Godes of Practices Preventing Falls in Housing Construction, Managing the Ride Safe in the Workjack Protect live edges and/or install temporary floors Work in scoordance with Safe Work Australia Codes of Practices Preventing Falls in Housing Construction, Managing the Ride of Falls in the Workplace				L L	
Suspended concrete	Back propping Uwe edges Openings in formwork	Collapse leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Fall leading to serious injury and/or fatality	Unlikely Possible	Extreme	н	Protect live edges and/or install temporary floors. Work in accordance with Safe Work Australia Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Workplace Protect live edges and/or install temporary floors Work in accordance with Safe Work Australia Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Workplace				L	
	Back propping Live edges Openings in formwork Transport, handling and erection	Collapse leading to serious injury and/or fatality fall leading to serious injury and/or fatality fall leading to serious injury and/or fatality fall leading to serious injury and/or fatality Collapse of structure or fall from height, leading	Unlikely Possible Likely	Extreme Extreme	H E	Protect live degas and/or install temporary floors. Workin sourdnane with Self Work Asstralla Code of Practice: Preventing Falls in Housing Construction, Managing the like of Falls in the Vorlytae: Protect live degas and/or install temporary floors Work in sourdnane with Self Work Australla Code of Practice: Preventing Falls in Housing Construction, Managing the like of Falls in the Vorlytae: Empage a Temporary Works Engineer to provide specific Engage a Temporary Works Engineer to provide specific device. Work in accordance with Self Work Australla Code device. Work in accordance with Self Work Australla Code with Common self-self-work Australia Loss which was a self-self-self-self-self-self-self-self-	Isolation	Extremely Rare	Extreme	L	
Framing	Back propping Live edges Openings in formwork Transport, handling and erection	Collapse leading to serious injury and/or fatality fall leading to serious injury and/or fatality fall leading to serious injury and/or fatality fall leading to serious injury and/or fatality Collapse of structure or fall from height, leading	Unlikely Possible Likely	Extreme Extreme	H E	Protect live deges and/or install temporary floors. Workin containan with Safe Work Australia Codes of Practice Preventing Falls in Housing Construction, Managing the Bids of Falls in the Workplace Protect live deges and/or install temporary floors Work in accordance with Safe Work Australia Codes of Practice Preventing Falls in Insusing Construction, Managing the Rids of Falls in the Workplace Engage a Temporary Works Engineer to provide specific advice. Work in accordance with Safe Work Australia Codes of Practice: Preventing Falls in Housing	Isolation	Extremely Rare	Extreme	L L	
Framing	Back propping Use edges Openings in formwork Transport, handling and erection of steel/timber framing	Collapse leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Collapse of structure or fall from height, leading to serious injury and/or fatality	Unlikely Possible Likely	Extreme Extreme	H E	Protect live deges and/or install temporary floors. Workin accordance with Self Work Asstralla Code of Practice: Preventing Falls in Housing Construction, Managing the Black of Falls in the Workplace Protect live deges and/or install temporary floors Work in coordance with Sale Work Australia Codes of Practice: Preventing Falls in Housing Construction, Managing the Histo of Falls in the Workplace Cragges a Temporary Works Engineer to provide specific advice. Work in accordance with Sale Work Australia Codes of Practice: Preventing Falls in Books of Codes of Practice: Preventing Falls in Books of Processing Codes of Codes of Practice: Preventing Falls in South Codes of Practice: Preventing Falls in Codes Code	Isolation	Extremely Rare	Extreme	L	
Framing OPERATION (in service)	Back propping Use edges Openings in formwork Transport, handling and erection of see!/timber framing Services/infrastructure is fit for	Collapse leading to serious injury and/or fatality fall leading to serious injury and/or fatality fall leading to serious injury and/or fatality fall leading to serious injury and/or fatality Collapse of structure or fall from height, leading	Unlikely Possible Likely Possible	Extreme Extreme Extreme	H E	Protect live deges and/or install temporary floors. Workin accordance with Sef Work Asstralla Code of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Vorlpiace Protect live deges and/or install temporary floors Work in accordance with Sef Work Asstralla Code of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Vorlpiace Engage a Temporary Works Engineer to provide specific Engage a Temporary Works Engineer to provide specific Services. Work in accordance with Sef Work Asstralla Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Services. Provided Services Infrastructure designed by a competent person	Isolation Engineering	Extremely Rare Extremely Rare	Extreme Extreme	L	
Framing	Back propping Use edges Openings in formwork Transport, handling and erection of steel/timber framing Services/infrastructure is fit for purpose and safe to use	Collapse leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Collapse of structure or fall from height, leading to serious injury and/or fatality	Unlikely Possible Likely	Extreme Extreme	H E	Protect live deges and/or install temporary floors. Workin accordance with Self Work Asstralla Code of Practice: Preventing Falls in Housing Construction, Managing the Black of Falls in the Workplace Protect live deges and/or install temporary floors Work in coordance with Sale Work Australia Codes of Practice: Preventing Falls in Housing Construction, Managing the Histo of Falls in the Workplace Cragges a Temporary Works Engineer to provide specific advice. Work in accordance with Sale Work Australia Codes of Practice: Preventing Falls in Books of Codes of Practice: Preventing Falls in Books of Processing Codes of Codes of Practice: Preventing Falls in South Codes of Practice: Preventing Falls in Codes Code	Isolation	Extremely Rare	Extreme	L L	
Framing OPERATION (in service)	Back propping Live edges Openings in formwork Transport, handling and erection of steel/timber framing Services/infrastructure is fit for purpose and safe to use Structure is fit for purpose and	Collapse leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Collapse of structure or fall from height, leading to serious injury and/or fatality Loss of amenity Collapse leading to serious injury and/or Collapse leading to serious injury and/or	Unlikely Possible Likely Possible Unlikely	Extreme Extreme Extreme Major	H H	Protect live degas and/or install temporary floors. Workin consordance with 5 and Verification (1974) and the control of the province of Practice Preventing Falls in Nousing Construction, Managing the Risk of Falls in the Verificate Control of the Protect live degas and/or install temporary floors Work in accordance with 5 and Verification (1974) and the Control of Practice: Preventing Falls in Housing Construction, Managing the Talls in the Verification of Falls in the Verification of Falls in the Verification of Verification with 5 and Verification (1974) and Verification of Verification with 5 and Verification (1974) and Verification of Verification with 5 and Verification (1974) and Verification of Verification (1974) and Verification (Isolation Engineering Engineering	Extremely Rare Extremely Rare Extremely Rare	Extreme Extreme Extreme	L	
Framing OPERATION (in service)	Back propping Use edges Openings in formwork Transport, handling and erection of steel/timber framing Services/infrastructure is fit for purpose and safe to use	Collapse lealing to serious injury and/or fatality Fall leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Collapse of structure or fall from height, leading to serious injury and/or fatality Loss of amenity	Unlikely Possible Likely Possible	Extreme Extreme Extreme	H E	Protect live degas and/or install temporary floors. Workin accordance with 5rd levok Asstralla Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Vorlytake of Protect live degas and/or install temporary floors Work in accordance with 5rd levok Asstralla Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Vorlytake Construction, Working Construction, Working Construction, Managing the Risk of Falls in the Vorlytake Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace in accordance with Tref Workplace Construction, Managing the Risk of Falls in the Workplace in accordance with relevant Australian Standards, MCC and recognised engineering principles.	Isolation Engineering	Extremely Rare Extremely Rare	Extreme Extreme	L L	
Framing OPERATION (in service) Performance	Back propping Use edges Use edges Openings in formwork Transport, handling and erection of steel/timber framing Services/Infrastructure is fit for purpose and safe to use Structure is fit for purpose and safe Alterations and additions	Collapse leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Collapse of structure or fall from height, leading to serious injury and/or fatality Loss of amenity Collapse leading to serious injury and/or fatality Collapse leading to serious injury and/or fatality Collapse leading to serious injury and/or Golapse leading to serious injury and/or Collapse leading to serious injury and/or	Unlikely Possible Likely Possible Unlikely Unlikely	Extreme Extreme Extreme Major Catastrophic	H H	Protect live deges and/or install temporary floors. Workin accordance with 5rd levels Asstralla Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Vorlytake of Protect live deges and/or install temporary floors Work in accordance with 5rd levels Asstralla Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Vorlytake Construction, Working Construction, Working Construction, Managing the Risk of Falls in the Vorlytake Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in Construction, Managing the Risk of Falls in Construction, Workplace with relevant Australian Standards, NCC and recognised engineering principles. Structure designed by a competent person in accordance with relevant Australian Standards, NCC and recognised engineering principles.	Isolation Engineering Engineering Engineering	Extremely Rare Extremely Rare Extremely Rare	Extreme Extreme Extreme Catastrophic	L	
Framing OPERATION (in service)	Back propping Use edges Openings in formwork Transport, handling and erection of steel/timber framing Services/infrastructure is fit for purpose and safe to use Structure is fit for purpose and safe to use	Collapse leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Collapse of structure or fall from height, leading to serious injury and/or fatality Loss of amenity Collapse leading to serious injury and/or fatality Collapse leading to serious injury and/or fatality	Unlikely Possible Likely Possible Unlikely	Extreme Extreme Extreme Major	H H	Protect live degas and/or install temporary floors. Workin consortance with 5 relivent Asstralia Code of Practice: Preventing Falls in Neurise Construction, Managing the Risk of Falls in the Verlopiace. Protect live degas and/or install temporary floors Work in accordance with 5 relivend Asstralia Codes of Practice: Preventing Falls in Neurise; Construction, Managing the Karlon Falls in the Verlopiace Construction, Managing the Construction of Practice: Preventing Falls in Neurise; Construction, Managing the Sall of Falls in the Verlopiace Construction, Managing the Risk of Falls in the Verlopiace Construction, Managing the Risk of Falls in the Verlopiace Construction, Managing the Risk of Falls in the Verlopiace Construction, Managing the Risk of Falls in the Verlopiace Construction, Managing the Risk of Falls in the Verlopiace Construction, Managing the Risk of Falls in the Verlopiace Construction, Managing the Risk of Falls in the Verlopiace Construction, Managing the Risk of Falls in the Verlopiace Construction, Managing the Risk of Falls in the Verlopiace Construction of Construction Construction of Construction	Isolation Engineering Engineering	Extremely Rare Extremely Rare Extremely Rare	Extreme Extreme Extreme	L	
Framing OPERATION (in service) Performance	Back propping Use edges Use edges Openings in formwork Transport, handling and erection of steel/timber framing Services/Infrastructure is fit for purpose and safe to use Structure is fit for purpose and safe Alterations and additions	Collapse leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Collapse of structure or fall from height, leading to serious injury and/or fatality Loss of amenity Collapse leading to serious injury and/or fatality Collapse leading to serious injury and/or fatality Collapse leading to serious injury and/or Golapse leading to serious injury and/or Collapse leading to serious injury and/or	Unlikely Possible Likely Possible Unlikely Unlikely	Extreme Extreme Extreme Major Catastrophic	H H	Protect live deges and/or install temporary floors. Workin accordance with 5rd levels Asstralla Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Vorlytake of Protect live deges and/or install temporary floors Work in accordance with 5rd levels Asstralla Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Vorlytake Construction, Working Construction, Working Construction, Managing the Risk of Falls in the Vorlytake Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in Construction, Managing the Risk of Falls in Construction, Workplace with relevant Australian Standards, NCC and recognised engineering principles. Structure designed by a competent person in accordance with relevant Australian Standards, NCC and recognised engineering principles.	Isolation Engineering Engineering Engineering	Extremely Rare Extremely Rare Extremely Rare	Extreme Extreme Extreme Catastrophic	L	
Framing OPERATION (in service) Performance	Back propping Use edges Use edges Openings in formwork Transport, handling and erection of steel/timber framing Services/Infrastructure is fit for purpose and safe to use Structure is fit for purpose and safe to se	Collapse leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Collapse of structure or fall from height, leading to serious injury and/or fatality Loss of amenity Collapse leading to serious injury and/or fatality	Unlikely Possible Likely Possible Unlikely Unlikely	Extreme Extreme Extreme Major Catastrophic	H H	Protect live degas and/or install temporary floors. Workin accordance with 5rd levels Asstalla Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Vorlpiace Protect live degas and/or install temporary floors Work in accordance with 5rd levels Asstalla Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Vorlpiace Engage a Temporary Works Engineer to provide specific addies, Work in accordance with 5rd levels Australia Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace in Accordance with 5rd levels and the Workplace Construction, Managing the Risk of Falls in the Workplace in accordance with relevant Australian Standards, NCC and recognised engineering principles Structure designed by a competent person in accordance with relevant Australian Standards, NCC and recognised engineering principles Structure designeed by a competent person in accordance with relevant Australian Standards, NCC and recognised engineering principles Structure designed by a competent person in accordance with relevant Australian Standards, NCC and recognised engineering principles Structure designeed by a competent person in accordance with relevant Australian Standards, NCC and recognised engineering principles Structure designeed by a competent person in accordance with relevant Australian Standards, NCC and recognised engineering principles Structure designeed by a competent person in accordance with relevant Australian Standards, NCC and recognised engineering principles Structure designeed by a competent person in accordance with relevant Australian Standards, NCC, and recognised engineering principles Structure designeed by a competent person in accordance with relevant Australian Standards, NCC, and recognised engineering principles Structure designeed by a competent person in accordance with relevant Australian Standards, NCC, and Recog	Isolation Engineering Engineering Engineering	Extremely Rare Extremely Rare Extremely Rare	Extreme Extreme Extreme Catastrophic	L	
Framing OPERATION (in service) Performance	Back propping Use edges Openings in formwork Transport, handling and erection of steel/timber framing Services/infrastructure is fit for purpose and safe to use Structure is fit for purpose and safe to use Alterations and additions affecting structure Alterations affecting civil or	Collapse leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Collapse of structure or fall from height, leading to serious injury and/or fatality Loss of amenity Collapse leading to serious injury and/or fatality Collapse leading to serious injury and/or fatality Impaired functionality, reduced safety leading Impaired functionality, reduced safety leading	Unlikely Possible Likely Possible Unlikely Unlikely Possible	Extreme Extreme Extreme Major Catastrophic Extreme	H	Protect live deges and/or install temporary floors. Workin consortance with 5 ref Work Asstralla Code of Practice: Preventing Falls in Neuring Construction, Managing the Kind of Falls in the Workplace. Protect live deges and/or install temporary floors Work in accordance with 5 ref Work Asstralla Code of Practice: Preventing Falls in Neuring Construction, Managing the Kind of Falls in the Workplace. Engage a Temporary Works Engineer to provide specific Engage a Temporary Works Engineer to provide specific Engage a Temporary Works Engineer to provide specific Construction, Managing the Risk of Falls in the Workplace. Construction, Managing the Risk of Falls in the Workplace of the Construction, Managing the Risk of Falls in the Workplace in accordance with Televant Asstralla Standards, Not Canding Construction, Managing the Risk of Falls in the Workplace of the Construction, Managing the Risk of Falls in the Workplace of the Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace Construction of the Managing the Risk of Falls in the Workplace Construction of the Managing the Risk of Falls in the Workplace Construction of the Managing the Risk of Falls in the Workplace Construction of the Managing the Risk of Falls in the Workplace Construction of the Managing the Risk of Falls in the Workplace Construction of the Managing the Risk of Falls in the Workplace Construction of the Managing the Risk of Falls in the Workplace Construction of the Managing the Risk of Falls in the Workplace Construction	Isolation Engineering Engineering Engineering Engineering	Extremely Rare Extremely Rare Extremely Rare Extremely Rare Extremely Rare	Extreme Extreme Extreme Catastrophic Extreme	L	
Framing OPERATION (in service) Performance	Back propping Use edges Openings in formwork Transport, handling and erection of steel/timber framing Services/infrastructure is fit for purpose and safe to use Structure is fit for purpose and safe to safe safe to safe safe safe safe safe safe safe safe	Collapse leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Fall leading to serious injury and/or fatality Collapse of structure or fall from height, leading to serious injury and/or fatality Loss of amenity Collapse leading to serious injury and/or fatality Impaired functionality, reduced safety leading to serious injury and/or fatality	Unlikely Possible Likely Possible Unlikely Unlikely Possible	Extreme Extreme Extreme Major Catastrophic Extreme	H	Protect live degas and/or install temporary floors. Workin accordance with 5rd levels Asstalla Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Vorlpiace Protect live degas and/or install temporary floors Work in accordance with 5rd levels Asstalla Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Vorlpiace Engage a Temporary Works Engineer to provide specific addies, Work in accordance with 5rd levels Australia Codes of Practice: Preventing Falls in Housing Construction, Managing the Risk of Falls in the Workplace Construction, Managing the Risk of Falls in the Workplace in Accordance with 5rd levels and the Workplace Construction, Managing the Risk of Falls in the Workplace in accordance with relevant Australian Standards, NCC and recognised engineering principles Structure designed by a competent person in accordance with relevant Australian Standards, NCC and recognised engineering principles Structure designeed by a competent person in accordance with relevant Australian Standards, NCC and recognised engineering principles Structure designed by a competent person in accordance with relevant Australian Standards, NCC and recognised engineering principles Structure designeed by a competent person in accordance with relevant Australian Standards, NCC and recognised engineering principles Structure designeed by a competent person in accordance with relevant Australian Standards, NCC and recognised engineering principles Structure designeed by a competent person in accordance with relevant Australian Standards, NCC and recognised engineering principles Structure designeed by a competent person in accordance with relevant Australian Standards, NCC, and recognised engineering principles Structure designeed by a competent person in accordance with relevant Australian Standards, NCC, and recognised engineering principles Structure designeed by a competent person in accordance with relevant Australian Standards, NCC, and Recog	Isolation Engineering Engineering Engineering Engineering	Extremely Rare Extremely Rare Extremely Rare Extremely Rare Extremely Rare	Extreme Extreme Extreme Catastrophic Extreme	L	

REV	DESCRIPTION	DATE
0	BUILDING APPROVAL	7/09/22
1	REVISED FOR BUILDING APPROVAL	17/02/25


Saltmarsh & Escobar Consulting Engineers


Leigh 0400 024 463


Noe 0416 074 935


ers	IS	
		ADD
	&	,
463	Ľ	
935		
om		

	CLIENT:		SHEET:	DRAWN:		DESIGNED:	VERIFIED:	DA	
		LIDDELOW	SAFETY IN DESIGN		NE	NE		-	12/04/22
3				SCALE:		NTC	SIZE:	4.2	
,	ADDRESS:		PROJECT NAME:			N.T.S		A3	
X		44 RIVIERA DRIVE	UNIT DEVELOPMENT	S&E REF:			DRAWING:		REVISION:
-		OLD BEACH	ISSUE: BUILDING APPROVAL	2	20)38	C00	4	1









LONGITUDINAL SECTION - CL1


SCALES: HORIZONTAL 1:250 VERTICAL 1:50


R	REV	DESCRIPTION	DATE
	0	BUILDING APPROVAL	7/09/22
	1 REVISED FOR BUILDING APPROVAL		17/02/25

Saltmarsh & Escobar Consulting Engineer Leigh 0400 024 46: Noe 0416 074 93: info@lsandne.com

LIDDELO
ESS:
44 RIVIER
OLD BEA

CLIENT:	SHEET:	DRAWN:	DESIGNED:	VERIFIED:	DATE:
LIDDELOW	LONGITUDINAL SECTION	NE	NE	-	12/04/22
		SCALE:		SIZE:	
ADDRESS:	PROJECT NAME:		AS SHOWN	A3	}
44 RIVIERA DRIVE	UNIT DEVELOPMENT	S&E REF:		DRAWING:	REVISION:
OLD BEACH	ISSUE: BUILDING APPROVAL	220)38	C104	1





Ch 35.00 m

Leigh 0400 024 463 Noe 0416 074 935

IENT:	SHEET:	DRAWN:	DESIGNED:	VERIFIED:	DATE:
LIDDELOW	CROSS SECTIONS PLAN 2	NE	NE	-	12/04/22
		SCALE:	1.100	SIZE:	
DDRESS:	PROJECT NAME:		1:100	<i>F</i>	1 3
44 RIVIERA DRIVE	UNIT DEVELOPMENT	S&E REF:		DRAWING:	REVISION:
OLD BEACH	ISSUE: BUILDING APPROVAL	220	038	C106	5 1

Ch 45.00 m

32.937 33.201

33.20

3.00

32.906

.67


32.

89 32.91

32.

3.00 3.67


REV	DESCRIPTION	DATE		
0	0 BUILDING APPROVAL			
1	1 REVISED FOR BUILDING APPROVAL			




17/02/25

REVISED FOR BUILDING APPROVAL

П	CLIENT:	SHEET:	DRAWN:	DESIGNED:	VERIFIED:	DATE:
	LIDDELOW	CROSS SECTIONS PLAN 3	NE	NE	-	12/04/22
1	ADDRESS	DDQ ISST NAME	SCALE:	1:100	SIZE: A3	,
	ADDRESS:	PROJECT NAME:		1.100	A	•
٠	44 RIVIERA DRIVE	UNIT DEVELOPMENT	S&E REF:		DRAWING:	REVISION:
	OLD BEACH	ISSUE: BUILDING APPROVAL	220	038	C107	1 1



CONNOLLY KEY JOINT +
REMOVABLE PVC CAPPING



TYPICAL CONCRETE PAVEMENT

SCALE 1:10

CONTROL JOINT 'c'

SCALE 1:10 NOTE: 24m CENTRES SAWN JOINT 's'

DATE: 12/04/22

REVISION:

A3

DRAWING:

C108

DESIGNED:

22038

1:10


SCALE 1:10 NOTE: 6m CENTRES


REV	DESCRIPTION	DATE
0	BUILDING APPROVAL	7/09/22
1	REVISED FOR BUILDING APPROVAL	17/02/25


Saltmarsh & Escobar Consulting Engineers

Leigh 0400 024 463
Noe 0416 074 935
info@learden.com

NT:	SHEET:	DRAWN:
LIDDELOW	DETAILS PLAN 1	
		SCALE:
RESS:	PROJECT NAME:	00.122.
44 RIVIERA DRIVE	UNIT DEVELOPMENT	S&E REF:
OLD BEACH	ISSUE: BUILDING APPROVAL	2









Submission to Planning Authority Notice

Application details

Council Planning Permit No. DA 2025/022

Council notice date 25/02/2025

TasWater Reference No. TWDA 2025/00177-BTN

Date of response 04/03/2025

TasWater Contact Timothy Carr

Phone No. 0419 306 130

Response issued to

Council name BRIGHTON COUNCIL

Contact details development@brighton.tas.gov.au

Development details

Address 44 RIVIERA DR, OLD BEACH

Property ID (PID) 9962130

Description of development Multiple Dwellings x 2

Schedule of drawings/documents

Prepared by	Drawing/document No.	Revision No.	Issue date
S & E	Services Plan – C103	1	17/02/2025
Stuart Bowling Building Design	Proposed Floor Plan – DWG No; 0130 – DAO3	А	17/02/2025

Conditions

Pursuant to the *Water and Sewerage Industry Act* 2008 (TAS) Section 56P(1) TasWater imposes the following conditions on the permit for this application:

CONNECTIONS, METERING & BACKFLOW

 A suitably sized water supply with metered connections and sewerage system and connections to the development must be designed and constructed to TasWater's satisfaction and be in accordance with any other conditions in this permit.



2. Any removal/supply and installation of water meters and/or the removal of redundant and/or installation of new and modified property service connections must be carried out by TasWater at the developer's cost.

Advice; The sewer lot connection/inspection opening is to be relocated clear of the stair area.

3. Prior to commencing construction of the development, any water connection utilised for construction must have a backflow prevention device and water meter installed, to the satisfaction of TasWater.

DEVELOPER CHARGES

- 4. Prior to TasWater issuing a Certificate(s) for Certifiable Work (Building) and/or (Plumbing), the applicant or landowner as the case may be, must pay a developer charge totalling \$1,054.20 to TasWater for water infrastructure for 0.600 additional Equivalent Tenements, indexed by the Consumer Price Index All groups (Hobart) from the date of this Submission to Planning Authority Notice until the date it is paid to TasWater.
- 5. Prior to TasWater issuing a Certificate(s) for Certifiable Work (Building) and/or (Plumbing), the applicant or landowner as the case may be, must pay a developer charge totalling \$1,757.00 to TasWater for sewerage infrastructure for 1.00 additional Equivalent Tenements, indexed by the Consumer Price Index All groups (Hobart) from the date of this Submission to Planning Authority Notice until the date it is paid to TasWater.

DEVELOPMENT ASSESSMENT FEES

6. The applicant or landowner as the case may be, must pay a development assessment fee of \$242.85 to TasWater, as approved by the Economic Regulator and the fee will be indexed, until the date paid to TasWater.

The payment is required within 30 days of the issue of an invoice by TasWater.

Advice

General

For information on TasWater development standards, please visit https://www.taswater.com.au/building-and-development/technical-standards For application forms please visit

https://www.taswater.com.au/building-and-development/development-application-form

Developer Charges

For information on Developer Charges please visit the following webpage https://www.taswater.com.au/building-and-development/developer-charges

Water Submetering

As of July 1 2022, TasWater's Sub-Metering Policy no longer permits TasWater sub-meters to be installed for new developments. Please ensure plans submitted with the application for Certificate(s) for Certifiable Work (Building and/or Plumbing) reflect this. For clarity, TasWater does not object to private sub-metering arrangements. Further information is available on our website (www.taswater.com.au) within our Sub-Metering Policy and Water Metering Guidelines.



Service Locations

Please note that the developer is responsible for arranging to locate the existing TasWater infrastructure and clearly showing it on the drawings. Existing TasWater infrastructure may be located by a surveyor and/or a private contractor engaged at the developers cost to locate the infrastructure.

- (a) A permit is required to work within TasWater's easements or in the vicinity of its infrastructure. Further information can be obtained from TasWater.
- (b) TasWater has listed a number of service providers who can provide asset detection and location services should you require it. Visit https://www.taswater.com.au/building-and-development/service-locations for a list of companies.
- (c) Sewer drainage plans or Inspection Openings (IO) for residential properties are available from your local council.

Declaration

The drawings/documents and conditions stated above constitute TasWater's Submission to Planning Authority Notice.